



NOT TO SCALE, FOR ILLUSTRATION ONLY

TANK INSIDE DIAMETER	MINIMUM BURY DEPTH	HALF ROUND DEADMAN	#5 REBAR EMBEDDED	ALTERNATE DEADMAN RECTANGULAR	MIN. SPACE BETWEEN MULT. TANKS	ALL ANCHORS SIDE PROJECTION	SLAB ANCHOR ONLY-END PROJECTION	FRP STRAP LENGTH	CABLE LENGTH (PER SIDE)	APPROX. GRAVEL REQD. PER LINEAR FOOT OF TANK LENGTH
8'	24"	9"x18"	2	12"x18"	3'	18"	18"	181"	12'	2 CUBIC YARDS
10'	24"	12"x24"	3	12"x24"	4'	24"	24"	225"	14'	3 CUBIC YARDS
11'	24"	18"x36"	5	12"x36"	6'	36"	36"	271"	16'	5 CUBIC YARDS
12'	24"	18"x36"	5	12"x36"	6'	36"	36"	271"	18'	5 CUBIC YARDS
13'	24"	24"x48"	7	12"x48"	8'	48"	48"	271"	20'	6 CUBIC YARDS

- 1 WHEN TANKS ARE EMPTY AND GROUND WATER IS EXPECTED NO HIGHER THAN SPRING LINE (STANDARD CONDITIONS).
- 2 HALF ROUND FIBERGLASS DEADMAN ANCHOR FORMS ARE AVAILABLE WITH YOUR TANK ORDER.
- 3 USE FULL SLAB ANCHOR IF GROUND WATER IS ANTICIPATED ABOVE SPRING LINE (EXTREME CONDITIONS).

DARCO INC
UNDERGROUND TANKAGE

Rev Date	ANTI-FLOTATION ANCHORS CARBON STEEL HARDWARE	Rev. No.
11/10/09	Drawing No.	T

980 Darco Drive, Bennett, Colorado 80102
 800-232-8660 (phone) 303-644-5001 (fax)
 www.darcoinc.com